ERDF/Creative Quarter: Castle Approach - Friar Lane

Metres

0 5 10 15 30

Ramp:
Sett paved ramps to be provided onto raised carriageway

North Side:
Widened and upgraded in Yorkstone paving slabs. Street trees introduced. Parking removed creating space for outdoor economic activity, e.g. licensed cafe areas

Ramp:
Sett paved ramps to be provided onto raised carriageway

Carriageway:
Raised block paving to almost level with footway (25mm kerb face).

Ramp:
Sett paved ramps to be provided onto raised carriageway

Carriageway:
Raised block paving to almost level with footway (25mm kerb face).

Feature Open Space:
Yorkstone feature paving with raised tegula block paved carriageway almost level with footway (25mm kerb face). Incorporating tree, and optional benches and cycle parking in positions to be agreed.

South Side:
Existing footway and kerb-line to remain, with existing vehicle cross-over revised. Opportunity for further tree

© Crown Copyright and database right 2014. Ordnance Survey Licence number 100019317

Key:

- New pink granite kerb
- Yorkstone paving slabs for footway
- Rustic block paving for carriageway
- Tumbled concrete setts
- Existing street lighting column
- Existing tree to be retained
- New tree in tree grill (indicative, optional)
- New tree in raised kerbs (indicative, optional)
- Bike stands (indicative, optional)
- Bench (indicative, optional)
- Existing kerbline

Nottingham City Council