My Ref: RS/ TCS0041/ Public
Your Ref: Shelton St
Contact: Paul Williams
Email: paul.williams@nottinghamcity.gov.uk

Owner / Occupier
Shelton Street Area

Traffic & Safety
Development Department
Nottingham City Council
Loxley House
Station Street
Nottingham
NG2 3NG

Tel: 0115 8765227
www.nottinghamcity.gov.uk

16 June 2014

Dear Citizen

Shelton Street Area - Road Safety Improvements

Re: Nottingham City Council (Shelton Street) proposed Traffic Calming (TCS0041)

Nottingham City Council has secured funding to alter the traffic calming features on Shelton Street. The existing speed cushions which were installed as part of the redevelopment of the Sytner BMW site in 2005, allow some vehicles to drive between the cushions with little impact on their speed.

To address this issue it is proposed to replace the speed cushions with round top road humps. These are the same features that are in place along Abbotsford Drive. The road humps will be constructed in asphalt to a height of approximately 70mm above the existing road level; they will span the full width of the road and will be to a depth of approximately 3.7 metres.

We are also aware of the difficulties being experienced when crossing Abbotsford Drive near its junction with Shelton Street. The raised land around the boundary of the public house, which includes mature trees, impacts on the visibility between motorists turning left into Abbotsford Drive and pedestrians waiting to cross in a south easterly direction at the tactile paving.

It is proposed to tighten the radius of the kerb line at the junction of Abbotsford Drive and to move the tactile paved crossing point closer to Shelton Street where visibility between motorists and pedestrians will be better. It will also mean that the crossing point will be on the pedestrian desire line for anyone walking along Shelton Street.

To summarise, the following works are proposed (please see the attached drawing – HD/TCS0041/03);

- Replace four pairs of speed cushions with round top road humps.
- Narrow the junction mouth of Abbotsford Drive and relocate the crossing point closer to Shelton Street.
- All lining will be renewed as part of the works.

Before proceeding further with these proposals and in accordance with statutory procedures and policies, we now wish to consider your views regarding this matter. Whilst it may not be possible to agree to all your suggestions, they will be incorporated into the proposals wherever appropriate and where budget allows.

please turn over

Any comments or objections to the proposals should be received by **Monday 14 July 2014**, either by letter or e-mail.

In the meantime if you have any general queries or comments or would like further information please contact me on **0115 8765227** or by email: **paul.williams@nottinghamcity.gov.uk**

Yours faithfully,



Paul Williams
Traffic & Safety

Enc: A3 Colour drawing of the proposed Road Safety Improvements